



BEAM SCHEDULE (2.OE)

- 21: 2 - 1 3/4" x 14" LVL - 8'0"
- 22: 2 - 1 3/4" x 11 7/8" LVL - 14'0"
- 23: 2 - 1 3/4" x 11 7/8" LVL - 10'0"
- 24: 2 - 1 3/4" x 14" LVL - 8'0"
- 25: 2 - 1 3/4" x 14" LVL - 20'0"
- 26: 1 - 1 3/4" x 14" LVL - 6'0"
- 27: 1 - 1 3/4" x 14" LVL - 18'0"
- 28: 1 - 1 3/4" x 14" LVL - 16'0"
- 29: 2 - 1 3/4" x 14" LVL - 18'0"
- 30: 1 - 1 3/4" x 14" LVL - 6'0"
- 31: 4 - 1 3/4" x 14" LVL - 18'0"
- 32: 1 - 1 3/4" x 14" LVL - 5'0"
- 33: 1 - 1 3/4" x 14" LVL - 12'0"
- 34: 1 - 1 3/4" x 14" LVL - 7'0"

LVL BEAMS FLUSH UNLESS NOTED
 APP - AS PER PLAN
 BBO - BEAM BY OTHERS

ALPA JOIST SCHEDULE

- J9M - 14" QF5-A314M @ 12" O.C.
- J10M - 14" QF5-A314M @ 16" O.C.
- J9A - 14" QF5-A314 @ 12" O.C.
- J10A - 14" QF5-A314 @ 16" O.C.
- J9B - 14" QF5-B314 @ 12" O.C.
- J10B - 14" QF5-B314 @ 16" O.C.

53 : W/One row of 2x6 Strongbacks.

SUBFLOOR : 3/4" Glued + Nailed

HANGER SCHEDULE

- LT 2514 ----- TM (H1)
- LF 2514 ----- FM (H2)
- L55UH 310 ----- FM (H3)
- HU5 1.81/10 ----- FM (LVL) (H4)
- HGU5 410 ----- FM (LVL) (H5)

RIMBOARD - 1 - 1/8" x 14" 0.5.B.

RULES FOR JOIST WITH OPENINGS:

The web on one side of the opening cannot be more than two feet longer than the other side after field trimming.

A minimum of two feet of web must be left on each side of the opening after field trimming.

1 - 2x6 SPF #2 SQUASH BLOCK REQ'D ON ONE SIDE OF EACH JOIST UNDER LOAD BEARING WALLS. MULTIPLE SQUASH BLOCKS REQ'D UNDER CONCENTRATED POINT LOADS.

Client: GormanMazzon Limited		Job Desc.: Figliomeni Residence	
Address: 446 Spadina Road, Suite 207 Toronto, Ontario M5P-3M2		Site Information: Main Floor Framing Plan 215 Orr Avenue Woodbridge, Ontario	
Telephone: (416) 818-5049	Fax: N/A	Telephone:	Fax:
Contact:	Sales: Argo - John D.	Telephone:	Contact:
Scale: N.T.S.	Date: June 28, 2005.	Drawn By: Alpa Floor System Inc.	Job # P-093-05

